Client: XM8 ONLINE Property: 123 Flood Way

Fredericton, NB E3B 1B5

Operator: DAVID.SO

Estimator: DS

Type of Estimate: Flood

Date Entered: 7/16/2023 Date Assigned:
Date Est. Completed: 8/31/2023 Date Job Completed:

Price List: NBFR8X_SEP23

Labor Efficiency: Restoration/Service/Remodel

Estimate: R_1-S-BD-AA_NBFR

R_1-S-BD-AA_NBFR

StructureLevelLineItems

Formula 0" x 0" x 0"



DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
1. Seal & paint window sill	55.00 LF	0.00	2.50	0.00	27.50	165.00
2. Window sill - stain grade	55.00 LF	0.00	4.09	0.00	45.00	269.95
3. Vinyl window, horizontal sliding, 12-23 sf	11.00 EA	0.00	412.31	0.00	907.08	5,442.49
4. Smoke detector - High grade	1.00 EA	0.00	87.09	0.00	17.42	104.51
5. Fluorescent - two tube - 6' - fixture w/lens	1.00 EA	0.00	143.48	0.00	28.70	172.18
6. Clothes dryer vent - installed	1.00 EA	0.00	75.02	0.00	15.00	90.02
7. Stain & finish handrail - wall mounted	15.00 LF	0.00	2.12	0.00	6.36	38.16
8. Handrail - detailed profile - softwood - wall mounted	15.00 LF	0.00	18.42	0.00	55.26	331.56
9. Stairway - 3' wide (8' rise plus joist)	1.00 EA	0.00	722.96	0.00	144.60	867.56
10. Truss - 6/12 slope - heavy loading	495.14 LF	0.00	10.35	0.00	1,024.94	6,149.64
11. 2" x 4" lumber (.667 BF per LF)	131.82 LF	0.00	2.58	0.00	68.02	408.12
12. 2" x 6" lumber (1 BF per LF)	61.80 LF	0.00	3.04	0.00	37.58	225.45
13. Framing hurricane tie	17.00 EA	0.00	8.08	0.00	27.48	164.84
14. Sheathing - plywood - 5/8" CDX	1,376.00 SF	0.00	2.86	0.00	787.08	4,722.44
15. Laminated - High grade - comp. shingle rfg w/ felt	14.00 SQ	0.00	323.02	0.00	904.46	5,426.74
16. Drip edge	136.00 LF	0.00	2.94	0.00	79.96	479.80
17. Flexible gas supply line connector - 1/2" - 25" to 48"	1.00 EA	0.00	51.06	0.00	10.22	61.28
18. Water heater - 50 gallon - Gas - 6 yr	1.00 EA	0.00	1,462.04	0.00	292.40	1,754.44
19. Black pipe with fitting and hanger, 1"	38.01 LF	0.00	13.39	0.00	101.80	610.75
20. Furnace vent - rain cap and storm collar, 5"	1.00 EA	0.00	73.08	0.00	14.62	87.70
21. Furnace vent - double wall, 5"	9.00 LF	0.00	29.80	0.00	53.64	321.84
22. Exterior faucet / hose bibb	2.00 EA	0.00	60.68	0.00	24.28	145.64
23. Seal & paint wood shelving, 12"-24" width	25.00 LF	0.00	4.44	0.00	22.20	133.20
24. Shelving - 16" - in place	25.00 LF	0.00	11.55	0.00	57.76	346.51
R_1-S-BD-AA_NBFR					9/18/2023	Page: 2

${\bf CONTINUED - Structure Level Line Items}$

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
25. Seal/prime (1 coat) then paint (1 coat) the surface area	122.00 SF	0.00	0.98	0.00	23.92	143.48
26. 1/2" drywall - hung, taped, heavy texture, ready for paint	122.00 SF	0.00	3.36	0.00	81.98	491.90
27. Door knob - interior - High grade	1.00 EA	0.00	62.41	0.00	12.48	74.89
28. Interior door unit - High grade	1.00 EA	0.00	366.18	0.00	73.24	439.42
29. Paint door/window trim & jamb - 2 coats (per side)	2.00 EA	0.00	31.36	0.00	12.54	75.26
30. Paint door slab only - 2 coats (per side)	2.00 EA	0.00	38.93	0.00	15.58	93.44
31. Stud wall - 2" x 6" - 16" oc	160.00 SF	0.00	4.00	0.00	128.00	768.00
32. Stud wall - 2" x 4" - 16" oc	1,117.18 SF	0.00	2.60	0.00	580.94	3,485.61
33. Batt insulation - 10" - R30 - paper / foil faced	1,083.58 SF	0.00	2.60	0.00	563.46	3,380.77
34. Batt insulation - 10" - R30 - paper / foil faced	900.00 SF	0.00	2.60	0.00	468.00	2,808.00
35. Blown-in insulation - 24" depth - R66	900.00 SF	0.00	3.73	0.00	671.40	4,028.40
36. Furnace - forced air - high efficiency - 100,000 BTU	1.00 EA	0.00	4,143.66	0.00	828.74	4,972.40
37. Ductwork system - hot or cold air - 1200 to 1599 SF home	1.00 EA	0.00	5,046.68	0.00	1,009.34	6,056.02
38. Thermostat - High grade	1.00 EA	0.00	156.81	0.00	31.36	188.17
39. Sheathing - OSB - 3/4" - tongue and groove	990.00 SF	0.00	2.93	0.00	580.14	3,480.84
40. Joist - floor or ceiling - 2x10 - w/blocking - 16" oc	900.00 SF	0.00	4.75	0.00	855.00	5,130.00
41. 2" x 6" lumber - redwood (1 BF per LF)	120.40 LF	0.00	5.85	0.00	140.86	845.20
42. Ceiling fan without light	1.00 EA	0.00	258.02	0.00	51.60	309.62
43. Exterior light fixture	2.00 EA	0.00	83.35	0.00	33.34	200.04
44. Door lockset & deadbolt - exterior	2.00 EA	0.00	105.01	0.00	42.00	252.02
45. Exterior door - metal - insulated - flush or panel style	2.00 EA	0.00	481.10	0.00	192.44	1,154.64
46. 6-0 6-8 vinyl sliding patio door	1.00 EA	0.00	1,142.67	0.00	228.54	1,371.21
47. Stud wall - 2" x 6" - 16" oc	1,083.58 SF	0.00	4.00	0.00	866.86	5,201.18
48. Eavestrough/downspout - aluminum - up to 5"	113.80 LF	0.00	8.52	0.00	193.92	1,163.50
49. Soffit & fascia - metal - 2' overhang	142.00 LF	0.00	18.61	0.00	528.52	3,171.14
50. Roof vent - turtle type - Metal	2.58 EA	0.00	67.32	0.00	34.74	208.43
51. Attic vent - gable end - vinyl	6.00 EA	0.00	148.94	0.00	178.72	1,072.36
52. House wrap (air/moisture barrier)	758.51 SF	0.00	0.32	0.00	48.54	291.26

${\bf CONTINUED - Structure Level Line Items}$

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
53. Sheathing - plywood - 1/2" CDX	758.51 SF	0.00	2.41	0.00	365.60	2,193.61
54. Synthetic stucco - additional charge for raised trim	151.70 LF	0.00	8.37	0.00	253.94	1,523.67
55. Metal lath & stucco	758.51 SF	0.00	8.86	0.00	1,344.08	8,064.48
56. Roofing felt - 15 lb.	3.30 SQ	0.00	35.93	0.00	23.72	142.29
57. Brick veneer	325.07 SF	0.00	22.27	0.00	1,447.86	8,687.17
58. Sheathing - OSB - 1/2"	325.07 SF	0.00	1.61	0.00	104.68	628.04
59. Phone, TV, or speaker outlet	2.00 EA	0.00	17.77	0.00	7.10	42.64
60. Grounding rod - copper clad with clamp, 8'	1.00 EA	0.00	104.37	0.00	20.88	125.25
61. Breaker panel - 100 amp	1.00 EA	0.00	800.22	0.00	160.04	960.26
62. Meter mast for overhead power - 2" conduit	1.00 EA	0.00	492.80	0.00	98.56	591.36
63. Meter base and main disconnect - 100 to 125 amp	1.00 EA	0.00	401.37	0.00	80.28	481.65
64. Phone / low voltage copper wiring	40.00 LF	0.00	0.99	0.00	7.92	47.52
65. Trunk cable - aluminum - 4 wire 4/0	40.00 LF	0.00	13.24	0.00	105.92	635.52
66. Phone, TV, or speaker outlet	4.00 EA	0.00	17.77	0.00	14.22	85.30
67. Exterior outlet or switch	2.00 EA	0.00	20.75	0.00	8.30	49.80
68. Rewire\wire - avg. residence - boxes & wiring	1,800.00 SF	0.00	3.58	0.00	1,288.80	7,732.80
69. Phone / low voltage copper wiring	40.00 LF	0.00	0.99	0.00	7.92	47.52
70. Dumpster load - Approx. 30 yards, 5-7 tons of debris	4.00 EA	861.00	0.00	0.00	688.80	4,132.80
71. Seal & paint wood shelving, 12"-24" width	4.00 LF	0.00	4.44	0.00	3.56	21.32
72. Shelving - 16" - in place	4.00 LF	0.00	11.55	0.00	9.24	55.44
73. Closet rod	4.00 LF	0.00	4.75	0.00	3.80	22.80
74. Seal/prime (1 coat) then paint (1 coat) the surface area	104.00 SF	0.00	0.98	0.00	20.38	122.30
75. 1/2" drywall - hung, taped, floated, ready for paint	104.00 SF	0.00	2.67	0.00	55.54	333.22
76. Door knob - interior	1.00 EA	0.00	47.96	0.00	9.60	57.56
77. Interior door unit	1.00 EA	0.00	365.09	0.00	73.02	438.11
78. Paint door/window trim & jamb - 2 coats (per side)	2.00 EA	0.00	31.36	0.00	12.54	75.26
79. Paint door slab only - 2 coats (per side)	2.00 EA	0.00	38.93	0.00	15.58	93.44
Totals: StructureLevelLineItems				0.00	19,461.44	116,768.15

Bath

Formula 8' 1" x 5' 1" x 8'

210.67 SF Walls

251.76 SF Walls & Ceiling

4.57 SY Flooring

64.67 SF Long Wall

26.33 LF Ceil. Perimeter

41.09 SF Ceiling

41.09 SF Floor

26.33 LF Floor Perimeter

40.67 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
80. Wall veneer panels - cultured marble	55.00 SF	0.00	25.32	0.00	278.52	1,671.12
81. Mortar bed for tile	55.00 SF	0.00	8.81	0.00	96.92	581.47
82. Towel bar	1.00 EA	0.00	36.59	0.00	7.32	43.91
83. Seal & paint wood shelving, 12"-24" width	12.00 LF	0.00	4.44	0.00	10.66	63.94
84. Shelving - 16" - in place	12.00 LF	0.00	11.55	0.00	27.72	166.32
85. Towel ring	1.00 EA	0.00	36.64	0.00	7.32	43.96
86. Toilet paper holder	1.00 EA	0.00	33.18	0.00	6.64	39.82
87. Outlet	2.00 EA	0.00	13.27	0.00	5.30	31.84
88. Mirror - 1/4" plate glass	6.00 SF	0.00	18.73	0.00	22.48	134.86
89. Rough in plumbing - per fixture - w/PEX	0.75 EA	0.00	576.31	0.00	86.44	518.67
90. Rough in plumbing - per fixture - w/PEX	0.75 EA	0.00	576.31	0.00	86.44	518.67
91. Rough in plumbing - per fixture - w/PEX	0.25 EA	0.00	576.31	0.00	28.82	172.90
92. Rough in plumbing - per fixture - w/PEX	0.25 EA	0.00	576.31	0.00	28.82	172.90
93. Toilet seat	1.00 EA	0.00	55.84	0.00	11.16	67.00
94. Toilet	1.00 EA	0.00	519.17	0.00	103.84	623.01
95. Bathtub	1.00 EA	0.00	920.28	0.00	184.06	1,104.34
96. Shower curtain rod	1.00 EA	0.00	34.52	0.00	6.90	41.42
97. Tub/shower faucet	1.00 EA	0.00	327.22	0.00	65.44	392.66
98. Ductwork - flexible - non-insulated - 3" round	10.00 LF	0.00	6.57	0.00	13.14	78.84
99. Bathroom ventilation fan	1.00 EA	0.00	120.98	0.00	24.20	145.18
100. Light bar - 5 lights	1.00 EA	0.00	103.99	0.00	20.80	124.79
101. Door knob - interior	1.00 EA	0.00	47.96	0.00	9.60	57.56
102. Paint door slab only - 2 coats (per side)	2.00 EA	0.00	38.93	0.00	15.58	93.44
103. Paint door/window trim & jamb - 2 coats (per side)	2.00 EA	0.00	31.36	0.00	12.54	75.26
104. Interior door unit	1.00 EA	0.00	365.09	0.00	73.02	438.11

CONTINUED - Bath

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
105. Ground fault interrupter (GFI) outlet	1.00 EA	0.00	37.00	0.00	7.40	44.40
106. Vanity	3.00 LF	0.00	231.30	0.00	138.78	832.68
107. Countertop - solid surface - High grade	6.00 SF	0.00	96.99	0.00	116.38	698.32
108. Sink faucet - Bathroom	1.00 EA	0.00	226.94	0.00	45.38	272.32
109. Rough in plumbing - per fixture - w/PEX	0.75 EA	0.00	576.31	0.00	86.44	518.67
110. Rough in plumbing - per fixture - w/PEX	0.25 EA	0.00	576.31	0.00	28.82	172.90
111. Sink - single	1.00 EA	0.00	291.28	0.00	58.26	349.54
112. Wallpaper border - Standard grade	6.58 LF	0.00	2.62	0.00	3.44	20.68
113. Wallpaper - Standard grade	52.67 SF	0.00	2.16	0.00	22.76	136.53
114. Seal the surface area w/latex based stain blocker - one coat	52.67 SF	0.00	0.63	0.00	6.64	39.82
115. Seal/prime (1 coat) then paint (1 coat) the surface area	158.00 SF	0.00	0.98	0.00	30.96	185.80
116. 1/2" drywall - hung, taped, heavy texture, ready for paint	210.67 SF	0.00	3.36	0.00	141.58	849.43
117. Stain & finish baseboard	26.33 LF	0.00	1.51	0.00	7.96	47.72
118. Baseboard - 3 1/4" stain grade	26.33 LF	0.00	5.68	0.00	29.92	179.47
119. 1/2" drywall - hung, taped, heavy texture, ready for paint	41.09 SF	0.00	3.36	0.00	27.62	165.68
120. Seal the surface area w/latex based stain blocker - one coat	41.09 SF	0.00	0.63	0.00	5.18	31.07
121. Paint the surface area - one coat	41.09 SF	0.00	0.69	0.00	5.68	34.03
122. Tile floor covering - High grade	10.27 SF	0.00	12.77	0.00	26.24	157.39
123. Sand & finish wood floor (natural finish)	20.55 SF	0.00	3.58	0.00	14.72	88.29
124. Oak flooring - select grade - no finish	20.55 SF	0.00	9.85	0.00	40.48	242.90
125. Pad - rebond, 3/8", 7 lb.	11.81 SF	0.00	0.97	0.00	2.30	13.76
126. Carpet - High grade	11.81 SF	0.00	7.66	0.00	18.10	108.56
Totals: Bath				0.00	2,098.72	12,591.95

Bath2

Formula 8' 1" x 5' 1" x 8'

210.67 SF Walls

251.76 SF Walls & Ceiling

4.57 SY Flooring

64.67 SF Long Wall

26.33 LF Ceil. Perimeter

41.09 SF Ceiling

41.09 SF Floor

26.33 LF Floor Perimeter

40.67 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
127. Wall veneer panels - cultured marble	55.00 SF	0.00	25.32	0.00	278.52	1,671.12
128. Mortar bed for tile	55.00 SF	0.00	8.81	0.00	96.92	581.47
129. Towel bar	1.00 EA	0.00	36.59	0.00	7.32	43.91
130. Seal & paint wood shelving, 12"-24" width	12.00 LF	0.00	4.44	0.00	10.66	63.94
131. Shelving - 16" - in place	12.00 LF	0.00	11.55	0.00	27.72	166.32
132. Towel ring	1.00 EA	0.00	36.64	0.00	7.32	43.96
133. Toilet paper holder	1.00 EA	0.00	33.18	0.00	6.64	39.82
134. Outlet	2.00 EA	0.00	13.27	0.00	5.30	31.84
135. Mirror - 1/4" plate glass	6.00 SF	0.00	18.73	0.00	22.48	134.86
136. Rough in plumbing - per fixture - w/PEX	0.75 EA	0.00	576.31	0.00	86.44	518.67
137. Rough in plumbing - per fixture - w/PEX	0.75 EA	0.00	576.31	0.00	86.44	518.67
138. Rough in plumbing - per fixture - w/PEX	0.25 EA	0.00	576.31	0.00	28.82	172.90
139. Rough in plumbing - per fixture - w/PEX	0.25 EA	0.00	576.31	0.00	28.82	172.90
140. Toilet seat	1.00 EA	0.00	55.84	0.00	11.16	67.00
141. Toilet	1.00 EA	0.00	519.17	0.00	103.84	623.01
142. Bathtub	1.00 EA	0.00	920.28	0.00	184.06	1,104.34
143. Shower curtain rod	1.00 EA	0.00	34.52	0.00	6.90	41.42
144. Tub/shower faucet	1.00 EA	0.00	327.22	0.00	65.44	392.66
145. Ductwork - flexible - non-insulated - 3" round	10.00 LF	0.00	6.57	0.00	13.14	78.84
146. Bathroom ventilation fan	1.00 EA	0.00	120.98	0.00	24.20	145.18
147. Light bar - 5 lights	1.00 EA	0.00	103.99	0.00	20.80	124.79
148. Door knob - interior	1.00 EA	0.00	47.96	0.00	9.60	57.56
149. Paint door slab only - 2 coats (per side)	2.00 EA	0.00	38.93	0.00	15.58	93.44
150. Paint door/window trim & jamb - 2 coats (per side)	2.00 EA	0.00	31.36	0.00	12.54	75.26
151. Interior door unit	1.00 EA	0.00	365.09	0.00	73.02	438.11

CONTINUED - Bath2

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
152. Ground fault interrupter (GFI) outlet	1.00 EA	0.00	37.00	0.00	7.40	44.40
153. Vanity	3.00 LF	0.00	231.30	0.00	138.78	832.68
154. Countertop - solid surface - High grade	6.00 SF	0.00	96.99	0.00	116.38	698.32
155. Sink faucet - Bathroom	1.00 EA	0.00	226.94	0.00	45.38	272.32
156. Rough in plumbing - per fixture - w/PEX	0.75 EA	0.00	576.31	0.00	86.44	518.67
157. Rough in plumbing - per fixture - w/PEX	0.25 EA	0.00	576.31	0.00	28.82	172.90
158. Sink - single	1.00 EA	0.00	291.28	0.00	58.26	349.54
159. Wallpaper border - Standard grade	6.58 LF	0.00	2.62	0.00	3.44	20.68
160. Wallpaper - Standard grade	52.67 SF	0.00	2.16	0.00	22.76	136.53
161. Seal the surface area w/latex based stain blocker - one coat	52.67 SF	0.00	0.63	0.00	6.64	39.82
162. Seal/prime (1 coat) then paint (1 coat) the surface area	158.00 SF	0.00	0.98	0.00	30.96	185.80
163. 1/2" drywall - hung, taped, heavy texture, ready for paint	210.67 SF	0.00	3.36	0.00	141.58	849.43
164. Stain & finish baseboard	26.33 LF	0.00	1.51	0.00	7.96	47.72
165. Baseboard - 3 1/4" stain grade	26.33 LF	0.00	5.68	0.00	29.92	179.47
166. 1/2" drywall - hung, taped, heavy texture, ready for paint	41.09 SF	0.00	3.36	0.00	27.62	165.68
167. Seal the surface area w/latex based stain blocker - one coat	41.09 SF	0.00	0.63	0.00	5.18	31.07
168. Paint the surface area - one coat	41.09 SF	0.00	0.69	0.00	5.68	34.03
169. Tile floor covering - High grade	10.27 SF	0.00	12.77	0.00	26.24	157.39
170. Sand & finish wood floor (natural finish)	20.55 SF	0.00	3.58	0.00	14.72	88.29
171. Oak flooring - select grade - no finish	20.55 SF	0.00	9.85	0.00	40.48	242.90
172. Pad - rebond, 3/8", 7 lb.	11.81 SF	0.00	0.97	0.00	2.30	13.76
173. Carpet - High grade	11.81 SF	0.00	7.66	0.00	18.10	108.56
Totals: Bath2				0.00	2,098.72	12,591.95

UtilityRoom

Formula 7' 1" x 5' 1" x 8'

194.67 SF Walls230.67 SF Walls & Ceiling4.00 SY Flooring56.67 SF Long Wall24.33 LF Ceil. Perimeter

36.01 SF Ceiling36.01 SF Floor24.33 LF Floor Perimeter40.67 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
174. Outlet	6.00 EA	0.00	13.27	0.00	15.92	95.54
175. Seal & paint wood shelving, 12"-24" width	11.00 LF	0.00	4.44	0.00	9.76	58.60
176. Shelving - 16" - in place	11.00 LF	0.00	11.55	0.00	25.42	152.47
177. Light fixture - Standard grade	1.00 EA	0.00	48.06	0.00	9.62	57.68
178. Door knob - interior	1.00 EA	0.00	47.96	0.00	9.60	57.56
179. Paint door slab only - 2 coats (per side)	2.00 EA	0.00	38.93	0.00	15.58	93.44
180. Paint door/window trim & jamb - 2 coats (per side)	2.00 EA	0.00	31.36	0.00	12.54	75.26
181. Interior door unit	1.00 EA	0.00	365.09	0.00	73.02	438.11
182. Wallpaper border - Standard grade	6.08 LF	0.00	2.62	0.00	3.18	19.11
183. Wallpaper - Standard grade	48.67 SF	0.00	2.16	0.00	21.02	126.15
184. Seal the surface area w/latex based stain blocker - one coat	48.67 SF	0.00	0.63	0.00	6.14	36.80
185. Seal/prime (1 coat) then paint (1 coat) the surface area	146.00 SF	0.00	0.98	0.00	28.62	171.70
186. 1/2" drywall - hung, taped, heavy texture, ready for paint	194.67 SF	0.00	3.36	0.00	130.82	784.91
187. Stain & finish baseboard	24.33 LF	0.00	1.51	0.00	7.34	44.08
188. Baseboard - 3 1/4" stain grade	24.33 LF	0.00	5.68	0.00	27.64	165.83
189. 1/2" drywall - hung, taped, heavy texture, ready for paint	36.01 SF	0.00	3.36	0.00	24.20	145.19
190. Seal the surface area w/latex based stain blocker - one coat	36.01 SF	0.00	0.63	0.00	4.54	27.23
191. Paint the surface area - one coat	36.01 SF	0.00	0.69	0.00	4.98	29.83
192. Tile floor covering - High grade	9.00 SF	0.00	12.77	0.00	22.98	137.91
193. Sand & finish wood floor (natural finish)	18.00 SF	0.00	3.58	0.00	12.88	77.32
194. Oak flooring - select grade - no finish	18.00 SF	0.00	9.85	0.00	35.46	212.76
195. Pad - rebond, 3/8", 7 lb.	10.35 SF	0.00	0.97	0.00	2.00	12.04
196. Carpet - High grade	10.35 SF	0.00	7.66	0.00	15.86	95.14
Totals: UtilityRoom				0.00	519.12	3,114.66

Bedroom2

Formula 10' 2" x 10' 2" x 8'

325.33 SF Walls

428.69 SF Walls & Ceiling

11.48 SY Flooring

81.33 SF Long Wall

40.67 LF Ceil. Perimeter

103.36 SF Ceiling 103.36 SF Floor

40.67 LF Floor Perimeter

81.33 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
197. Smoke detector	1.00 EA	0.00	60.40	0.00	12.08	72.48
198. Seal & paint wood shelving, 12"-24" width	5.00 LF	0.00	4.44	0.00	4.44	26.64
199. Shelving - 16" - in place	5.00 LF	0.00	11.55	0.00	11.56	69.31
200. Closet rod	5.00 LF	0.00	4.75	0.00	4.76	28.51
201. Outlet	6.00 EA	0.00	13.27	0.00	15.92	95.54
202. Light fixture	1.00 EA	0.00	63.51	0.00	12.70	76.21
203. Door knob - interior	1.00 EA	0.00	47.96	0.00	9.60	57.56
204. Paint bifold door set - slab only - 2 coats (per side)	2.00 EA	0.00	55.02	0.00	22.00	132.04
205. Bifold door set - Colonist - Double	1.00 EA	0.00	415.62	0.00	83.12	498.74
206. Paint door slab only - 2 coats (per side)	2.00 EA	0.00	38.93	0.00	15.58	93.44
207. Paint door/window trim & jamb - 2 coats (per side)	2.00 EA	0.00	31.36	0.00	12.54	75.26
208. Interior door unit	1.00 EA	0.00	365.09	0.00	73.02	438.11
209. Wallpaper border - Standard grade	10.17 LF	0.00	2.62	0.00	5.34	31.99
210. Wallpaper - Standard grade	81.33 SF	0.00	2.16	0.00	35.14	210.81
211. Seal the surface area w/latex based stain blocker - one coat	81.33 SF	0.00	0.63	0.00	10.24	61.48
212. Seal/prime (1 coat) then paint (1 coat) the surface area	244.00 SF	0.00	0.98	0.00	47.82	286.94
213. 1/2" drywall - hung, taped, heavy texture, ready for paint	325.33 SF	0.00	3.36	0.00	218.62	1,311.73
214. Stain & finish baseboard	40.67 LF	0.00	1.51	0.00	12.28	73.69
215. Baseboard - 3 1/4" stain grade	40.67 LF	0.00	5.68	0.00	46.20	277.21
216. 1/2" drywall - hung, taped, heavy texture, ready for paint	103.36 SF	0.00	3.36	0.00	69.46	416.75
217. Seal the surface area w/latex based stain blocker - one coat	103.36 SF	0.00	0.63	0.00	13.02	78.14
218. Paint the surface area - one coat	103.36 SF	0.00	0.69	0.00	14.26	85.58
219. Tile floor covering - High grade	25.84 SF	0.00	12.77	0.00	66.00	395.98
220. Sand & finish wood floor (natural finish)	51.68 SF	0.00	3.58	0.00	37.00	222.01

CONTINUED - Bedroom2

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
221. Oak flooring - select grade - no finish	51.68 SF	0.00	9.85	0.00	101.82	610.87
222. Pad - rebond, 3/8", 7 lb.	29.72 SF	0.00	0.97	0.00	5.76	34.59
223. Carpet - High grade	29.72 SF	0.00	7.66	0.00	45.54	273.20
Totals: Bedroom2				0.00	1,005.82	6,034.81



Kitchen Formula 11' 2" x 10' 2" x 8'

341.33 SF Walls

454.86 SF Walls & Ceiling

12.61 SY Flooring

89.33 SF Long Wall

42.67 LF Ceil. Perimeter

113.53 SF Ceiling 113.53 SF Floor

42.67 LF Floor Perimeter

81.33 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
224. 220 volt outlet	1.00 EA	0.00	33.10	0.00	6.62	39.72
225. Ground fault interrupter (GFI) outlet	2.00 EA	0.00	37.00	0.00	14.80	88.80
226. Outlet	4.00 EA	0.00	13.27	0.00	10.62	63.70
227. Outlet	2.00 EA	0.00	13.27	0.00	5.30	31.84
228. Rough in plumbing - per fixture - w/PEX	1.00 EA	0.00	576.31	0.00	115.26	691.57
229. Sink faucet - Kitchen	1.00 EA	0.00	267.94	0.00	53.58	321.52
230. Sink - double basin	1.00 EA	0.00	403.31	0.00	80.66	483.97
231. Fluorescent - two tube - 4' - fixture w/lens	1.00 EA	0.00	115.87	0.00	23.18	139.05
232. Cabinetry - lower (base) units	6.00 LF	0.00	245.56	0.00	294.68	1,768.04
233. Appliance water line - 1/4"	1.00 EA	0.00	65.80	0.00	13.16	78.96
234. Cabinet knob or pull	28.00 EA	0.00	9.57	0.00	53.60	321.56
235. Custom cabinets - wall units - 36" tall	14.00 LF	0.00	209.99	0.00	587.98	3,527.84
236. Cabinetry - laminate lower (base) units - High grade	16.00 LF	0.00	306.37	0.00	980.38	5,882.30
237. Microwave oven - over range w/built-in hood	1.00 EA	0.00	520.01	0.00	104.00	624.01
238. Countertop - solid surface - High grade	32.00 SF	0.00	96.99	0.00	620.74	3,724.42
239. Countertop - solid surface - High grade	12.00 SF	0.00	96.99	0.00	232.78	1,396.66
240. 110 volt copper wiring run, box and outlet	1.00 EA	0.00	75.59	0.00	15.12	90.71

CONTINUED - Kitchen

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
241. 110 volt copper wiring run, box and outlet	1.00 EA	0.00	75.59	0.00	15.12	90.71
242. 220 volt copper wiring run, box and receptacle	1.00 EA	0.00	212.95	0.00	42.60	255.55
243. Dishwasher - High grade	1.00 EA	0.00	1,089.48	0.00	217.90	1,307.38
244. Range - drop in	1.00 EA	0.00	1,690.61	0.00	338.12	2,028.73
245. Refrigerator - top freezer - 22 to 24 cf	1.00 EA	0.00	992.15	0.00	198.44	1,190.59
246. Wallpaper border - Standard grade	10.67 LF	0.00	2.62	0.00	5.60	33.56
247. Wallpaper - Standard grade	85.33 SF	0.00	2.16	0.00	36.86	221.17
248. Seal the surface area w/latex based stain blocker - one coat	85.33 SF	0.00	0.63	0.00	10.76	64.52
249. Seal/prime (1 coat) then paint (1 coat) the surface area	256.00 SF	0.00	0.98	0.00	50.18	301.06
250. 1/2" drywall - hung, taped, heavy texture, ready for paint	341.33 SF	0.00	3.36	0.00	229.38	1,376.25
251. Stain & finish baseboard	42.67 LF	0.00	1.51	0.00	12.88	77.31
252. Baseboard - 3 1/4" stain grade	42.67 LF	0.00	5.68	0.00	48.48	290.85
253. 1/2" drywall - hung, taped, heavy texture, ready for paint	113.53 SF	0.00	3.36	0.00	76.30	457.76
254. Seal the surface area w/latex based stain blocker - one coat	113.53 SF	0.00	0.63	0.00	14.30	85.82
255. Paint the surface area - one coat	113.53 SF	0.00	0.69	0.00	15.66	94.00
256. Tile floor covering - High grade	28.38 SF	0.00	12.77	0.00	72.48	434.89
257. Sand & finish wood floor (natural finish)	56.76 SF	0.00	3.58	0.00	40.64	243.84
258. Oak flooring - select grade - no finish	56.76 SF	0.00	9.85	0.00	111.82	670.91
259. Pad - rebond, 3/8", 7 lb.	32.64 SF	0.00	0.97	0.00	6.34	38.00
260. Carpet - High grade	32.64 SF	0.00	7.66	0.00	50.00	300.02
Totals: Kitchen				0.00	4,806.32	28,837.59



Bedroom3 Formula 14' 2" x 12' 2" x 8'

421.33 SF Walls 593.69 SF Walls & Ceiling

19.15 SY Flooring

113.33 SF Long Wall52.67 LF Ceil. Perimeter

ong Wall 97.33 SF Short Wall

172.36 SF Ceiling

52.67 LF Floor Perimeter

172.36 SF Floor

DESCRIPTION QTY REMOVE REPLACE TAX O&P TOTAL

CONTINUED - Bedroom3

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
261. Smoke detector	1.00 EA	0.00	60.40	0.00	12.08	72.48
262. Seal & paint wood shelving, 12"-24" width	5.00 LF	0.00	4.44	0.00	4.44	26.64
263. Shelving - 16" - in place	5.00 LF	0.00	11.55	0.00	11.56	69.31
264. Closet rod	5.00 LF	0.00	4.75	0.00	4.76	28.51
265. Outlet	6.00 EA	0.00	13.27	0.00	15.92	95.54
266. Light fixture	1.00 EA	0.00	63.51	0.00	12.70	76.21
267. Door knob - interior	1.00 EA	0.00	47.96	0.00	9.60	57.56
268. Paint bifold door set - slab only - 2 coats (per side)	2.00 EA	0.00	55.02	0.00	22.00	132.04
269. Bifold door set - Colonist - Double	1.00 EA	0.00	415.62	0.00	83.12	498.74
270. Paint door slab only - 2 coats (per side)	2.00 EA	0.00	38.93	0.00	15.58	93.44
271. Paint door/window trim & jamb - 2 coats (per side)	2.00 EA	0.00	31.36	0.00	12.54	75.26
272. Interior door unit	1.00 EA	0.00	365.09	0.00	73.02	438.11
273. Wallpaper border - Standard grade	13.17 LF	0.00	2.62	0.00	6.90	41.41
274. Wallpaper - Standard grade	105.33 SF	0.00	2.16	0.00	45.50	273.01
275. Seal the surface area w/latex based stain blocker - one coat	105.33 SF	0.00	0.63	0.00	13.28	79.64
276. Seal/prime (1 coat) then paint (1 coat) the surface area	316.00 SF	0.00	0.98	0.00	61.94	371.62
277. 1/2" drywall - hung, taped, heavy texture, ready for paint	421.33 SF	0.00	3.36	0.00	283.14	1,698.81
278. Stain & finish baseboard	52.67 LF	0.00	1.51	0.00	15.90	95.43
279. Baseboard - 3 1/4" stain grade	52.67 LF	0.00	5.68	0.00	59.84	359.01
280. 1/2" drywall - hung, taped, heavy texture, ready for paint	172.36 SF	0.00	3.36	0.00	115.82	694.95
281. Seal the surface area w/latex based stain blocker - one coat	172.36 SF	0.00	0.63	0.00	21.72	130.31
282. Paint the surface area - one coat	172.36 SF	0.00	0.69	0.00	23.78	142.71
283. Tile floor covering - High grade	43.09 SF	0.00	12.77	0.00	110.06	660.32
284. Sand & finish wood floor (natural finish)	86.18 SF	0.00	3.58	0.00	61.70	370.22
285. Oak flooring - select grade - no finish	86.18 SF	0.00	9.85	0.00	169.78	1,018.65
286. Pad - rebond, 3/8", 7 lb.	49.55 SF	0.00	0.97	0.00	9.62	57.68
287. Carpet - High grade	49.55 SF	0.00	7.66	0.00	75.92	455.47
Totals: Bedroom3				0.00	1,352.22	8,113.08

Bedroom

Formula 10' 2" x 10' 2" x 8'

325.33 SF Walls

428.69 SF Walls & Ceiling

11.48 SY Flooring

81.33 SF Long Wall

40.67 LF Ceil. Perimeter

103.36 SF Ceiling 103.36 SF Floor

40.67 LF Floor Perimeter

81.33 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
288. Smoke detector	1.00 EA	0.00	60.40	0.00	12.08	72.48
289. Seal & paint wood shelving, 12"-24" width	5.00 LF	0.00	4.44	0.00	4.44	26.64
290. Shelving - 16" - in place	5.00 LF	0.00	11.55	0.00	11.56	69.31
291. Closet rod	5.00 LF	0.00	4.75	0.00	4.76	28.51
292. Outlet	6.00 EA	0.00	13.27	0.00	15.92	95.54
293. Light fixture	1.00 EA	0.00	63.51	0.00	12.70	76.21
294. Door knob - interior	1.00 EA	0.00	47.96	0.00	9.60	57.56
295. Paint bifold door set - slab only - 2 coats (per side)	2.00 EA	0.00	55.02	0.00	22.00	132.04
296. Bifold door set - Colonist - Double	1.00 EA	0.00	415.62	0.00	83.12	498.74
297. Paint door slab only - 2 coats (per side)	2.00 EA	0.00	38.93	0.00	15.58	93.44
298. Paint door/window trim & jamb - 2 coats (per side)	2.00 EA	0.00	31.36	0.00	12.54	75.26
299. Interior door unit	1.00 EA	0.00	365.09	0.00	73.02	438.11
300. Wallpaper border - Standard grade	10.17 LF	0.00	2.62	0.00	5.34	31.99
301. Wallpaper - Standard grade	81.33 SF	0.00	2.16	0.00	35.14	210.81
302. Seal the surface area w/latex based stain blocker - one coat	81.33 SF	0.00	0.63	0.00	10.24	61.48
303. Seal/prime (1 coat) then paint (1 coat) the surface area	244.00 SF	0.00	0.98	0.00	47.82	286.94
304. 1/2" drywall - hung, taped, heavy texture, ready for paint	325.33 SF	0.00	3.36	0.00	218.62	1,311.73
305. Stain & finish baseboard	40.67 LF	0.00	1.51	0.00	12.28	73.69
306. Baseboard - 3 1/4" stain grade	40.67 LF	0.00	5.68	0.00	46.20	277.21
307. 1/2" drywall - hung, taped, heavy texture, ready for paint	103.36 SF	0.00	3.36	0.00	69.46	416.75
308. Seal the surface area w/latex based stain blocker - one coat	103.36 SF	0.00	0.63	0.00	13.02	78.14
309. Paint the surface area - one coat	103.36 SF	0.00	0.69	0.00	14.26	85.58
310. Tile floor covering - High grade	25.84 SF	0.00	12.77	0.00	66.00	395.98
311. Sand & finish wood floor (natural finish)	51.68 SF	0.00	3.58	0.00	37.00	222.01

CONTINUED - Bedroom

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
312. Oak flooring - select grade - no finish	51.68 SF	0.00	9.85	0.00	101.82	610.87
313. Pad - rebond, 3/8", 7 lb.	29.72 SF	0.00	0.97	0.00	5.76	34.59
314. Carpet - High grade	29.72 SF	0.00	7.66	0.00	45.54	273.20
Totals: Bedroom				0.00	1,005.82	6,034.81



Nook Formula 8' 1" x 6' 1" x 8'

226.67 SF Walls

275.84 SF Walls & Ceiling

5.46 SY Flooring

64.67 SF Long Wall

28.33 LF Ceil. Perimeter

49.17 SF Ceiling

49.17 SF Floor

28.33 LF Floor Perimeter

48.67 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
315. Outlet	4.00 EA	0.00	13.27	0.00	10.62	63.70
316. Light fixture - Standard grade	1.00 EA	0.00	48.06	0.00	9.62	57.68
317. Wallpaper border - Standard grade	7.08 LF	0.00	2.62	0.00	3.72	22.27
318. Wallpaper - Standard grade	56.67 SF	0.00	2.16	0.00	24.48	146.89
319. Seal the surface area w/latex based stain blocker - one coat	56.67 SF	0.00	0.63	0.00	7.14	42.84
320. Seal/prime (1 coat) then paint (1 coat) the surface area	170.00 SF	0.00	0.98	0.00	33.32	199.92
321. 1/2" drywall - hung, taped, heavy texture, ready for paint	226.67 SF	0.00	3.36	0.00	152.32	913.93
322. Stain & finish baseboard	28.33 LF	0.00	1.51	0.00	8.56	51.34
323. Baseboard - 3 1/4" stain grade	28.33 LF	0.00	5.68	0.00	32.18	193.09
324. 1/2" drywall - hung, taped, heavy texture, ready for paint	49.17 SF	0.00	3.36	0.00	33.04	198.25
325. Seal the surface area w/latex based stain blocker - one coat	49.17 SF	0.00	0.63	0.00	6.20	37.18
326. Paint the surface area - one coat	49.17 SF	0.00	0.69	0.00	6.78	40.71
327. Tile floor covering - High grade	12.29 SF	0.00	12.77	0.00	31.38	188.32
328. Sand & finish wood floor (natural finish)	24.59 SF	0.00	3.58	0.00	17.60	105.63
329. Oak flooring - select grade - no finish	24.59 SF	0.00	9.85	0.00	48.44	290.65
330. Pad - rebond, 3/8", 7 lb.	14.14 SF	0.00	0.97	0.00	2.74	16.46
331. Carpet - High grade	14.14 SF	0.00	7.66	0.00	21.66	129.97

CONTINUED - Nook

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
Totals: Nook				0.00	449.80	2,698.83



Hallway2

Formula 10' 2" x 3' x 8'

210.67 SF Walls

241.17 SF Walls & Ceiling

3.39 SY Flooring

81.33 SF Long Wall

26.33 LF Ceil. Perimeter

30.50 SF Ceiling 30.50 SF Floor

26.33 LF Floor Perimeter

24.00 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
332. Smoke detector	1.00 EA	0.00	60.40	0.00	12.08	72.48
333. Outlet	2.00 EA	0.00	13.27	0.00	5.30	31.84
334. Light fixture	1.00 EA	0.00	63.51	0.00	12.70	76.21
335. Wallpaper border - Standard grade	6.58 LF	0.00	2.62	0.00	3.44	20.68
336. Wallpaper - Standard grade	52.67 SF	0.00	2.16	0.00	22.76	136.53
337. Seal the surface area w/latex based stain blocker - one coat	52.67 SF	0.00	0.63	0.00	6.64	39.82
338. Seal/prime (1 coat) then paint (1 coat) the surface area	158.00 SF	0.00	0.98	0.00	30.96	185.80
339. 1/2" drywall - hung, taped, heavy texture, ready for paint	210.67 SF	0.00	3.36	0.00	141.58	849.43
340. Stain & finish baseboard	26.33 LF	0.00	1.51	0.00	7.96	47.72
341. Baseboard - 3 1/4" stain grade	26.33 LF	0.00	5.68	0.00	29.92	179.47
342. 1/2" drywall - hung, taped, heavy texture, ready for paint	30.50 SF	0.00	3.36	0.00	20.50	122.98
343. Seal the surface area w/latex based stain blocker - one coat	30.50 SF	0.00	0.63	0.00	3.84	23.06
344. Paint the surface area - one coat	30.50 SF	0.00	0.69	0.00	4.22	25.27
345. Tile floor covering - High grade	7.63 SF	0.00	12.77	0.00	19.48	116.92
346. Sand & finish wood floor (natural finish)	15.25 SF	0.00	3.58	0.00	10.92	65.52
347. Oak flooring - select grade - no finish	15.25 SF	0.00	9.85	0.00	30.04	180.25
348. Pad - rebond, 3/8", 7 lb.	8.77 SF	0.00	0.97	0.00	1.70	10.21
349. Carpet - High grade	8.77 SF	0.00	7.66	0.00	13.44	80.62
Totals: Hallway2				0.00	377.48	2,264.81

Bedroom4

Formula 14' 2" x 12' 2" x 8'

421.33 SF Walls

593.69 SF Walls & Ceiling

19.15 SY Flooring

113.33 SF Long Wall

52.67 LF Ceil. Perimeter

172.36 SF Ceiling 172.36 SF Floor

52.67 LF Floor Perimeter

97.33 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
350. Smoke detector	1.00 EA	0.00	60.40	0.00	12.08	72.48
351. Seal & paint wood shelving, 12"-24" width	5.00 LF	0.00	4.44	0.00	4.44	26.64
352. Shelving - 16" - in place	5.00 LF	0.00	11.55	0.00	11.56	69.31
353. Closet rod	5.00 LF	0.00	4.75	0.00	4.76	28.51
354. Outlet	6.00 EA	0.00	13.27	0.00	15.92	95.54
355. Light fixture	1.00 EA	0.00	63.51	0.00	12.70	76.21
356. Door knob - interior	1.00 EA	0.00	47.96	0.00	9.60	57.56
357. Paint bifold door set - slab only - 2 coats (per side)	2.00 EA	0.00	55.02	0.00	22.00	132.04
358. Bifold door set - Colonist - Double	1.00 EA	0.00	415.62	0.00	83.12	498.74
359. Paint door slab only - 2 coats (per side)	2.00 EA	0.00	38.93	0.00	15.58	93.44
360. Paint door/window trim & jamb - 2 coats (per side)	2.00 EA	0.00	31.36	0.00	12.54	75.26
361. Interior door unit	1.00 EA	0.00	365.09	0.00	73.02	438.11
362. Wallpaper border - Standard grade	13.17 LF	0.00	2.62	0.00	6.90	41.41
363. Wallpaper - Standard grade	105.33 SF	0.00	2.16	0.00	45.50	273.01
364. Seal the surface area w/latex based stain blocker - one coat	105.33 SF	0.00	0.63	0.00	13.28	79.64
365. Seal/prime (1 coat) then paint (1 coat) the surface area	316.00 SF	0.00	0.98	0.00	61.94	371.62
366. 1/2" drywall - hung, taped, heavy texture, ready for paint	421.33 SF	0.00	3.36	0.00	283.14	1,698.81
367. Stain & finish baseboard	52.67 LF	0.00	1.51	0.00	15.90	95.43
368. Baseboard - 3 1/4" stain grade	52.67 LF	0.00	5.68	0.00	59.84	359.01
369. 1/2" drywall - hung, taped, heavy texture, ready for paint	172.36 SF	0.00	3.36	0.00	115.82	694.95
370. Seal the surface area w/latex based stain blocker - one coat	172.36 SF	0.00	0.63	0.00	21.72	130.31
371. Paint the surface area - one coat	172.36 SF	0.00	0.69	0.00	23.78	142.71
372. Tile floor covering - High grade	43.09 SF	0.00	12.77	0.00	110.06	660.32
373. Sand & finish wood floor (natural finish)	86.18 SF	0.00	3.58	0.00	61.70	370.22

CONTINUED - Bedroom4

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
374. Oak flooring - select grade - no finish	86.18 SF	0.00	9.85	0.00	169.78	1,018.65
375. Pad - rebond, 3/8", 7 lb.	49.55 SF	0.00	0.97	0.00	9.62	57.68
376. Carpet - High grade	49.55 SF	0.00	7.66	0.00	75.92	455.47
Totals: Bedroom4				0.00	1,352.22	8,113.08



LivingRoom

Formula 18' 3" x 12' 2" x 8'

486.67 SF Walls 708.71 SF Walls & Ceiling 24.67 SY Flooring 146.00 SF Long Wall 60.83 LF Ceil. Perimeter 222.04 SF Ceiling222.04 SF Floor60.83 LF Floor Perimeter97.33 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
377. Outlet	8.00 EA	0.00	13.27	0.00	21.24	127.40
378. Light fixture	1.00 EA	0.00	63.51	0.00	12.70	76.21
379. Wallpaper border - Standard grade	15.21 LF	0.00	2.62	0.00	7.98	47.83
380. Wallpaper - Standard grade	121.67 SF	0.00	2.16	0.00	52.56	315.37
381. Seal the surface area w/latex based stain blocker - one coat	121.67 SF	0.00	0.63	0.00	15.34	91.99
382. Seal/prime (1 coat) then paint (1 coat) the surface area	365.00 SF	0.00	0.98	0.00	71.54	429.24
383. 1/2" drywall - hung, taped, heavy texture, ready for paint	486.67 SF	0.00	3.36	0.00	327.04	1,962.25
384. Paint crown moulding, oversized - one coat	60.83 LF	0.00	1.04	0.00	12.66	75.92
385. Crown moulding - 4 1/4" stain grade	60.83 LF	0.00	8.02	0.00	97.58	585.44
386. Stain & finish baseboard	60.83 LF	0.00	1.51	0.00	18.38	110.23
387. Baseboard - 3 1/4" stain grade	60.83 LF	0.00	5.68	0.00	69.10	414.61
388. 1/2" drywall - hung, taped, heavy texture, ready for paint	313.97 SF	0.00	3.36	0.00	210.98	1,265.92
389. Seal the surface area w/latex based stain blocker - one coat	313.97 SF	0.00	0.63	0.00	39.56	237.36
390. Paint the surface area - one coat	313.97 SF	0.00	0.69	0.00	43.32	259.96
391. Tile floor covering - High grade	55.51 SF	0.00	12.77	0.00	141.78	850.64
392. Sand & finish wood floor (natural finish)	111.02 SF	0.00	3.58	0.00	79.50	476.95
393. Oak flooring - select grade - no finish	111.02 SF	0.00	9.85	0.00	218.72	1,312.27
_1-S-BD-AA_NBFR					9/18/2023	Page: 18

${\bf CONTINUED - Living Room}$

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
394. Pad - rebond, 3/8", 7 lb.	63.84 SF	0.00	0.97	0.00	12.38	74.30
395. Carpet - High grade	63.84 SF	0.00	7.66	0.00	97.80	586.81
Totals: LivingRoom				0.00	1,550.16	9,300.70



Patio

Formula 5' 8" x 5' 8" x 8'

181.33 SF Walls

213.44 SF Walls & Ceiling

3.57 SY Flooring

45.33 SF Long Wall

22.67 LF Ceil. Perimeter

32.11 SF Ceiling 32.11 SF Floor

22.67 LF Floor Perimeter

45.33 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
396. Stain/finish deck handrail	12.75 LF	0.00	7.16	0.00	18.26	109.55
397. Deck guard rail - redwood	12.75 LF	0.00	54.09	0.00	137.94	827.59
398. Storm door assembly	1.00 EA	0.00	362.67	0.00	72.54	435.21
399. Stud wall - 2" x 6" - 16" oc	20.00 SF	0.00	4.00	0.00	16.00	96.00
400. 1" x 8" lumber (.667 BF per LF)	28.00 LF	0.00	4.49	0.00	25.14	150.86
401. Roofing felt - 15 lb.	0.24 SQ	0.00	35.93	0.00	1.72	10.34
402. Metal lath & stucco	28.00 SF	0.00	8.86	0.00	49.62	297.70
403. House wrap (air/moisture barrier)	12.00 SF	0.00	0.32	0.00	0.76	4.60
404. Brick veneer - High grade	12.00 SF	0.00	23.63	0.00	56.72	340.28
405. Outlet	1.00 EA	0.00	13.27	0.00	2.66	15.93
406. Ground fault interrupter (GFI) outlet	1.00 EA	0.00	37.00	0.00	7.40	44.40
407. Exterior light fixture - Standard grade	1.00 EA	0.00	65.65	0.00	13.14	78.79
408. Soffit - metal	32.11 SF	0.00	7.08	0.00	45.46	272.80
409. Sheathing - plywood - 1/2" CDX	76.67 SF	0.00	2.41	0.00	36.96	221.73
410. 2" x 4" lumber (.667 BF per LF)	23.28 LF	0.00	2.58	0.00	12.02	72.08
411. 2" x 6" lumber (1 BF per LF)	11.33 LF	0.00	3.04	0.00	6.88	41.32
412. Truss - 4/12 slope	22.67 LF	0.00	9.03	0.00	40.94	245.65
413. Laminated - High grade - comp. shingle rfg w/ felt	1.00 SQ	0.00	323.02	0.00	64.60	387.62
414. 6" x 6" square wood post (3 BF per LF)	17.00 LF	0.00	9.67	0.00	32.88	197.27
415. Framing hurricane tie	4.00 EA	0.00	8.08	0.00	6.46	38.78
Totals: Patio				0.00	648.10	3,888.50
_1-S-BD-AA_NBFR					9/18/2023	Page: 19

Hallway

Formula 15' 2" x 4' 1" x 8'

308.00 SF Walls 369.93 SF Walls & Ceiling 6.88 SY Flooring 121.33 SF Long Wall 38.50 LF Ceil. Perimeter 61.93 SF Ceiling61.93 SF Floor38.50 LF Floor Perimeter32.67 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
416. Smoke detector	1.00 EA	0.00	60.40	0.00	12.08	72.48
417. Outlet	2.00 EA	0.00	13.27	0.00	5.30	31.84
418. Light fixture	1.00 EA	0.00	63.51	0.00	12.70	76.21
419. Wallpaper border - Standard grade	9.63 LF	0.00	2.62	0.00	5.04	30.27
420. Wallpaper - Standard grade	77.00 SF	0.00	2.16	0.00	33.26	199.58
421. Seal the surface area w/latex based stain blocker - one coat	77.00 SF	0.00	0.63	0.00	9.70	58.21
422. Seal/prime (1 coat) then paint (1 coat) the surface area	231.00 SF	0.00	0.98	0.00	45.28	271.66
423. 1/2" drywall - hung, taped, heavy texture, ready for paint	308.00 SF	0.00	3.36	0.00	206.98	1,241.86
424. Stain & finish baseboard	38.50 LF	0.00	1.51	0.00	11.62	69.76
425. Baseboard - 3 1/4" stain grade	38.50 LF	0.00	5.68	0.00	43.74	262.42
426. 1/2" drywall - hung, taped, heavy texture, ready for paint	61.93 SF	0.00	3.36	0.00	41.62	249.70
427. Seal the surface area w/latex based stain blocker - one coat	61.93 SF	0.00	0.63	0.00	7.80	46.82
428. Paint the surface area - one coat	61.93 SF	0.00	0.69	0.00	8.54	51.27
429. Tile floor covering - High grade	15.48 SF	0.00	12.77	0.00	39.54	237.22
430. Sand & finish wood floor (natural finish)	30.97 SF	0.00	3.58	0.00	22.18	133.05
431. Oak flooring - select grade - no finish	30.97 SF	0.00	9.85	0.00	61.02	366.07
432. Pad - rebond, 3/8", 7 lb.	17.81 SF	0.00	0.97	0.00	3.46	20.74
433. Carpet - High grade	17.81 SF	0.00	7.66	0.00	27.28	163.70
Totals: Hallway				0.00	597.14	3,582.86



LivingRoom2

Formula 18' 3" x 12' 2" x 8'

486.67 SF Walls 708.71 SF Walls & Ceiling 24.67 SY Flooring 146.00 SF Long Wall 60.83 LF Ceil. Perimeter 222.04 SF Ceiling222.04 SF Floor60.83 LF Floor Perimeter97.33 SF Short Wall

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
434. Outlet	8.00 EA	0.00	13.27	0.00	21.24	127.40
435. Light fixture	1.00 EA	0.00	63.51	0.00	12.70	76.21
436. Wallpaper border - Standard grade	15.21 LF	0.00	2.62	0.00	7.98	47.83
437. Wallpaper - Standard grade	121.67 SF	0.00	2.16	0.00	52.56	315.37
438. Seal the surface area w/latex based stain blocker - one coat	121.67 SF	0.00	0.63	0.00	15.34	91.99
439. Seal/prime (1 coat) then paint (1 coat) the surface area	365.00 SF	0.00	0.98	0.00	71.54	429.24
440. 1/2" drywall - hung, taped, heavy texture, ready for paint	486.67 SF	0.00	3.36	0.00	327.04	1,962.25
441. Paint crown moulding, oversized - one coat	60.83 LF	0.00	1.04	0.00	12.66	75.92
442. Crown moulding - 4 1/4" stain grade	60.83 LF	0.00	8.02	0.00	97.58	585.44
443. Stain & finish baseboard	60.83 LF	0.00	1.51	0.00	18.38	110.23
444. Baseboard - 3 1/4" stain grade	60.83 LF	0.00	5.68	0.00	69.10	414.61
445. 1/2" drywall - hung, taped, heavy texture, ready for paint	222.04 SF	0.00	3.36	0.00	149.22	895.27
446. Seal the surface area w/latex based stain blocker - one coat	222.04 SF	0.00	0.63	0.00	27.98	167.87
447. Paint the surface area - one coat	222.04 SF	0.00	0.69	0.00	30.64	183.85
448. Tile floor covering - High grade	55.51 SF	0.00	12.77	0.00	141.78	850.64
449. Sand & finish wood floor (natural finish)	111.02 SF	0.00	3.58	0.00	79.50	476.95
450. Oak flooring - select grade - no finish	111.02 SF	0.00	9.85	0.00	218.72	1,312.27
451. Pad - rebond, 3/8", 7 lb.	63.84 SF	0.00	0.97	0.00	12.38	74.30
452. Carpet - High grade	63.84 SF	0.00	7.66	0.00	97.80	586.81
Totals: LivingRoom2				0.00	1,464.14	8,784.45
Labor Minimums Applied						

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
453. Mirror/shower door labour minimum	1.00 EA	0.00	111.12	0.00	22.22	133.34

CONTINUED - Labor Minimums Applied

DESCRIPTION	QTY	REMOVE	REPLACE	TAX	O&P	TOTAL
454. General labour - labour minimum	1.00 EA	0.00	30.64	0.00	6.12	36.76
Totals: Labor Minimums Applied				0.00	28.34	170.10
Line Item Totals: R 1-S-BD-AA NBFR				0.00	38,815.56	232,890.33

Grand Total Areas:

1,400.96	SF Walls SF Floor SF Long Wall	155.66	SF Ceiling SY Flooring SF Short Wall	543.83	SF Walls and Ceiling LF Floor Perimeter LF Ceil. Perimeter
	Floor Area Exterior Wall Area		Total Area Exterior Perimeter of Walls	0.00	Interior Wall Area
	Surface Area Total Ridge Length		Number of Squares Total Hip Length	0.00	Total Perimeter Length

Summary

Line Item Total	194,074.77
Overhead	19,407.78
Profit	19,407.78
Replacement Cost Value	\$232,890.33
Net Claim	\$232,890.33

DS

Recap of Taxes, Overhead and Profit

	Overhead (10%)	Profit (10%)
Line Items	19,407.78	19,407.78
Total	19,407.78	19,407.78

Recap by Room

Estimate: R_1-S-BD-AA_NBFR		
StructureLevelLineItems	97,306.71	50.14%
Bath	10,493.23	5.41%
Bath2	10,493.23	5.41%
UtilityRoom	2,595.54	1.34%
Bedroom2	5,028.99	2.59%
Kitchen	24,031.27	12.38%
Bedroom3	6,760.86	3.48%
Bedroom	5,028.99	2.59%
Nook	2,249.03	1.16%
Hallway2	1,887.33	0.97%
Bedroom4	6,760.86	3.48%
LivingRoom	7,750.54	3.99%
Patio	3,240.40	1.67%
Hallway	2,985.72	1.54%
LivingRoom2	7,320.31	3.77%
Labor Minimums Applied	141.76	0.07%
Subtotal of Areas	194,074.77	100.00%
Total	194,074.77	100.00%

Recap by Category

O&P Items	Total	%
APPLIANCES	4,358.05	1.87%
CABINETRY	16,402.34	7.04%
GENERAL DEMOLITION	3,444.00	1.48%
DOORS	6,274.25	2.69%
DRYWALL	19,604.75	8.42%
ELECTRICAL	10,893.95	4.68%
FLOOR COVERING - CARPET	3,396.32	1.46%
FLOOR COVERING - CERAMIC TILE	4,369.90	1.88%
FLOOR COVERING - WOOD	9,191.88	3.95%
FINISH CARPENTRY / TRIMWORK	5,521.35	2.37%
FINISH HARDWARE	937.97	0.40%
FRAMING & ROUGH CARPENTRY	29,411.85	12.63%
HEAT, VENT & AIR CONDITIONING	10,136.81	4.35%
INSULATION	8,760.87	3.76%
LABOUR ONLY	30.64	0.01%
LIGHT FIXTURES	1,561.90	0.67%
MASONRY	7,522.87	3.23%
MARBLE - CULTURED OR NATURAL	2,785.20	1.20%
MIRRORS & SHOWER DOORS	335.88	0.14%
PLUMBING	11,530.29	4.95%
PAINTING	9,123.28	3.92%
ROOFING	5,546.02	2.38%
SIDING	893.64	0.38%
SOFFIT, FASCIA, & EAVESTROUGH	3,839.54	1.65%
STAIRS	722.96	0.31%
STUCCO & EXTERIOR PLASTER	8,238.21	3.54%
TILE	969.10	0.42%
WINDOWS - SLIDING PATIO DOORS	1,142.67	0.49%
WINDOWS - VINYL	4,535.41	1.95%
WALLPAPER	2,592.87	1.11%
O&P Items Subtotal	194,074.77	83.33%
Overhead	19,407.78	8.33%
Profit	19,407.78	8.33%
Total	232,890.33	100.00%